

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
240 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-20,051-0006

LEASE NAME Hoffman

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 4 TWP. 24 RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-30-93

Plugging Completed 9-1-93

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	224'	none
				4 1/2"	3437'	390'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ foot to \_\_\_\_\_ foot each set. Bottom was plugged previously by another company. Shot @ 1900', 1000', 800', 700'.

Worked pipe, could not free. Spotted 35 sks @ 700'. Shot @ 390', pulled 3 joints. Pumped 155 sks @ 387'. Circulated 80 sks to surface & pulled rest of pipe. 60/40 pos 4% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) of CONSERVATION DIVISION of Wichita, Kansas facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19 93

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_

