

200 Colorado Derby Building
Wichita, Kansas 67202

15-155-19198-0001

API Number NONE
LEASE NAME Welch

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER Z=B
1980 Ft. from S Section Line
660 Ft. from E Section Line
SEC. 4 TWP. 24S RGE. 4 (S or W)

LEASE OPERATOR Producers Oil Company

ADDRESS 427 S. Boston - Suite 711 Tulsa, OK 74103-4199

PHONE# (918) 582-1188 OPERATORS LICENSE NO. 5235

County Rego
Date Well Completed March 21, 1938

Character of Well Oil

Plugging Commenced Oct 28, 1992

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed Oct 29, 1992

The plugging proposal was approved on September 1, 1992 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No

Producing Formation Miss Chat Depth to Top 3291 Bottom 3382 T.D. 3382

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss Chat	Gas, Oil, Water	3291	3382	13"	275	0
				7"	3299	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Ran bailer found TD @ 3382, dumped 200 gal sand top sand @ 3249. Dumped 10 sacks cement - Perforated 7" @ 580 fr. Halliburton pumped 50 sacks cement @ 580 feet. Ran bits 1" to 325 circulated cement to surface. Ran 1" outside 7" to 325 feet circulated current to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address P.O. Box 341, Canton, KS 67428


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Producers Oil Co. - Fee has been paid

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Richard N. Knoblock (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Richard N. Knoblock
(Address) 427 S. Boston, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 93



MY COMMISSION EXPIRES 8-7-96

