

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-155-20072-0000

LEASE NAME Hoffman #2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER _____

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 4 TWP. 24s RGE. 4w (E) or (W)

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, Ks. 67202 COUNTY Reno

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed _____

Character of Well _____

Plugging Commenced 12/18/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/30/86

Did you notify the KCC District Office prior to plugging this well? _____ Yes

Which KCC Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3353'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	258'	none
				8 5/8	2347'	1237'
				4 1/2"	3348'	2570'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet, each set.
Plugged bottom with sand to 3300' & 4 sacks cement. Shot pipe at 2704' & 2570'
Pulled 80 joints of 4 1/2". Shot pipe at 2003'. Pipe parted. Pulled 33 joints
of 8 5/8. Plugged well with 5 hulls, plug, & 150 sacks econolite cement.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1986

COPY

RECEIVED
 STATE CORPORATION COMMISSION
 My Commission Expires:

Irene Hoover
 Notary Public

4-6-87

PR 10 1987



CONSERVATION DIVISION
 Wichita, Kansas

ROTARY DRILLERS' LOG

OPERATOR: Rosen Oil Company
605 Sutton Place
Wichita, Kansas 67202

DRILLING COMMENCED: August 15, 1968

CONTRACTOR: Graves Drilling Co., Inc.
505 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: September 1, 1968

CASING RECORD: 13 Jts. 258' 10-3/4"
cemented with 300 sacks
116 Jts. 2345' 8-5/8"
cemented with 100 sacks
105 Jts. 3345' 4-1/2"
cemented with 100 sacks

LOCATION: Hoffman No. 2
NE SW NE
Section 4-22S-4W
Reno County, Kansas

0 - 213	Sand & sod
213 - 259	Shale & shells
259 - 415	Shale & salt
415 - 555	Salt & shale
555 - 965	Shale & lime
965 - 1350	Lime & shale
1350 - 1940	Shale & lime
1940 - 1999	Shale
1999 - 2412	Lime
2412 - 2692	Shale & lime
2692 - 2990	Lime
2990 - 3113	Lime & shale
3113 - 3299	Shale & lime
3299 - 3330	Lime & chert
3330 - 3430	Lime
3430	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Jah Graves
President

STATE OF KANSAS)
) ss:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 16th of September, 1968.

Betty Brandt
Betty Brandt Notary Public

My commission expires: May 9, 1971

RECEIVED SEP 17 1968