

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 8-9
LOCATION CSW-SE-NE
SEC. 14 TWP. 24 RGE. 11W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 8 Lease John Krey.

Operator Sinclair Oil & Gas Company Address P. O. Box 551.
Chase, Kansas.

Field _____ County Stafford.

Total Depth 3801' Feet.

Plugging Contractor West Supply Co., Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas.
(Describe Briefly the manner in which the well was plugged)

Surface pipe - 13" @ 257' c.w.c. 275 sx.. 7" set @ 2778' cem. 150 sx.
Sand back to 3760' and 6 sx. cem. with dump bailer. Shot 7" pipe off @
2681' and pulled up to approx. 1200' and pumped in 30 sx. of jell mud,
then pulled pipe out. Mud up to 255' from top, set plug, rock bridge and
30 sx. cem. with dump bailer. Mud to 30' from top, set plug, rock bridge
and 20 sx. cem. to base of cellar.

Mud was pumped with West Supply's own pump.

Milton Gehardt.
District Conservation Agent

Date 7-20-57

PLUGGING
FILE SEC 14 T. 24 R. 11W
BOOK PAGE 8 LINE 9

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1957

CONSERVATION DIVISION
Wichita, Kansas