

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 105-45

LOCATION NE-NE-SW

SEC. 14 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease B. McComb

Operator Standard Oil & Gas Co Address Box #7 Ellinwood - Kans

Field _____ County Stafford

Total Depth 3828 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 234 ft - Circulated with cement
7" casing set at 3785 ft - Filled back from bottom
to 3780 ft - Dumped 5 sacks of cement at 3780 ft
Shot off & Pulled the 7" casing - Filled with water
mud to 234 ft - Set Plug & 20 sacks of cement
at 234 ft. Mud to 30 ft - Plug & 10 sacks of
cement at the surface*

Frank Carroll 8-8-49

Plugging Contractor

RECEIVED

C. D. Stough -
District Conservation Agent

Conservation Div.

Date 8-5-49

AUG 8 - 1949

STATE CORPORATION
COMMISSION
KANSAS

L 42520

PLUGGING
FILE