

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Intent to Drill,  
filed June 6, 1967.

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Carter Well No. # 1

Location C NW SW Sec. 12 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 2580'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Edmiston Drilling Company, Inc.

Address: 425 First National Bank Bldg., Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour 1:30PM Day 9th Month June Year 1967

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole  
with drilling mud to 230', 1st cementing plug, bridge with 1/2 sack of hulls,  
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing  
plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar.  
Bridge and cement rat hole with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elovig  
Well Plugging Supervisor

DATE 6/13/67

INV. NO. 5378-W