

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

APR 24 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Messman-Rinehart Oil CompanyComplete Address: 1432 Wichita Plaza, Wichita, KansasLease Name Greenleaf Well No. # 1Location NE NE NE Sec. 13 Twp. 28 Rge. 7 (E) (W) WCounty Kingman Total Depth 2945Abandoned Oil Well Gas Well X Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Flint Engineering & Construction Co.Address: Box 980, El Dorado, Kansas License No. 547Operation Completed: Hour 4:00PM Day 22nd Month April Year 1964

The Above well was plugged as follows:

197' of 8 5/8" surface pipe, cement circulated. 2945' of 4 1/2" long string,
cemented with 50 sacks. Plug back to 2933'. Top perforation 2908'. Bottom
of the hole was sanded to 2900', and cemented with 3 sacks. Hole was
filled with mud to 250', with 10' rock bridge, and cemented with 40 sacks.
Hole was filled with mud to 40', with 10' of rock bridge, and cemented
with 10 sacks to base cellar.

2600' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/24/64INV. NO. 9022-WSigned: Archie Elving
Well Plugging Supervisor