



RECEIVED 12-21-67

DEC 21 1967 State Corporation Commission

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

CONSERVATION DIVISION  
Wichita, Kansas  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 11, 1967

15-155-2000B-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Charles D. Johnson

Complete Address: 523 W. Kansas Ave., Mc Pherson, Kansas 67460

Lease Name: Hensley Well No. 1

Location: C W/2 SE Sec. 14 Twp. 23 Rge. 4 (E)(W) X

County: Reno Total Depth 3720' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3700' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent