

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
FAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 31, 1965 STATE CORPORATION COMMISSION
JUN 3 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. O. C. Arnott of Bergman Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Arnott guarantees payment of the plugging fee.

Operator's full Name: Bergman Oil Company

Complete Address: 425 Union Center, Wichita, Kansas

Lease Name: Harnar Well No. 1

Location: C SE NW Sec. 14 Twp. 23 Rge. 4 CEX(W) X

County Reno Total Depth 3580' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Arnott was instructed to plug the well as follows:

Fill hole with mud to 255'. Push plug and 1/2 sack hulls to 255' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Alfred J. Roman
Conservation Division Agent