

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED  
212 INFORMATION COMMISSION  
NOV 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

October 14, 1968

15-155-30208-0001

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Fred Shaffer

Complete Address: Wolcott Bldg., Hutchinson, Kansas 67501

Lease Name: Wilson Well No. 1

Location: W/2 SW Sec. 23 Twp. 23 Rge. 4 (E)(W) X

County: Reno Total Depth 1854' Oil Well OWWO

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clark was instructed to plug the well as follows:

Push 4½" plug to 1670'. Fill hole with sand to 1650' and cement with  
3 sacks. Fill hole with mud to 250'. Set rock bridge from 250' to 240'  
and cement hole with 30 sacks cement. Fill hole with mud to 35'. Set  
rock bridge from 35' to 25' and cap hole with 15 sacks cement.

Very truly yours,

William J. Lorman  
Conservation Division Agent