

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 18, 1967

15-155-30155-0000

OCT 2 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling, Inc. this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol, Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Evans Well No. 4

Location: C E/2 E/2 NE Sec. 23 Twp. 23 Rge. 4 (W) X

County Reno Total Depth 3349' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

Fill hole with sand to 3280' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent