

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 106-1LOCATION CSE-SW-SWSEC. 14 TWP. 24 RGE. 11-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease M. Volker - "B"Operator Stanolind Oil & Gas Co. Address Box #7 - Ellinwood - KansasField _____ County StaffordTotal Depth 3827 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13'-266ft - Circulated with cement.
7" casing set at 3795ft - Plugged back from bottom
to 3795 with Chat - 5 sacks of cement dumped in the
7" casing at 3795ft - Shot off & pulled the 7" casing
filled with mud to 266ft. Rock Bridge & 20 sacks of
cement at 266ft - Mud to 30ft - Plug & 10 sacks
of cement at the surface

Pipe Pulling, Inc.

Plugging Contractors

C. M. Strong
District Conservation Agent

Date

8-17-498-21-49