

To: ² 040358
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,713 0000
C SE SW, SEC. 12, T 27 S, R 10 W/EX
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5992
Operator: Patton Oil Co.
Name & Address 672 W. 4th
Hoisington, KS 67544

Lease Name McMichael Well # 1-A
County Kingman 96.10
Well Total Depth 2957 PBD 1628 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Kansas

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Dallas
(company name) Kelso Casing Pulling (phone) _____

were: 4 1/2" @1649, Perf @1578-1600
35 sxs on bottom, 200# hulls, 12 gel, 110 sxs 60/40 poz

Plugging Proposal Received by Steve Van Gieson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 Day: 6 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT A 35 sk plug was pushed to 1357' to cover perforations. The
4 1/2" was pulled and recovered. The top was squeeze plugged through the
8 5/8" casing by pumping 200# hulls, 12 sxs gel, and 110 sxs 60/40 poz,
4% gel.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1987 08-18-87

Remarks: Allied #2276 MX 500 SI 0
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.
DATE 8-21-87 WK
INV. NO. 17910

Signed [Signature]
(TECHNICIAN)