

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-01980-00-00

Spot: SENESESE Sec 35 Twp 17 S Rng 21  E /  W  
693 Feet from  N /  S Line of Section  
161 Feet from  E /  W Line of Section

GPS: Lat: 38.522580 Long: 95.047240 Date: 3/21/16 1/25/16

Lease Name: Caylor Well #: K20

County: Miami Total Vertical Depth: 360 feet

Operator License No: 34372 String \_\_\_\_\_ Size \_\_\_\_\_ Depth \_\_\_\_\_ Pulled \_\_\_\_\_ Comments \_\_\_\_\_  
 Op Name: Freeman E. Jockish SURF - Casing \_\_\_\_\_ 8.000 \_\_\_\_\_ 20 \_\_\_\_\_ 0 \_\_\_\_\_ EST \_\_\_\_\_  
 Address 1: 3881 Bebee Point Dr. \_\_\_\_\_  
 Address 2: \_\_\_\_\_  
 City: Theodore \_\_\_\_\_  
 State: Al Zip Code: 36582 - \_\_\_\_\_

Well Type: OG - Oil & Gas UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 1/28/16 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 1/28/16 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Remove two loads of fluid from pit and haul to disposal well. Build location for drill rig. Backfill bermed area. Drill and wash to 180 ft and hit steel. Drill beside steel to 215 ft. Pull drill steel and and run 1" to 350 ft. Wash 1" to 360 ft and hit hard. Pump Portland cement from TD to surface. Pull pipe and top off well. Pump total of 153 sacks of cement. Well plugged. Finish smoothing out area where pits were backfilled.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract No. 38595. Control No. 20160022-001.GPS'ed by F.G. NAD 83. Reg. Sect. Docket No. 16-CONS-639-CMSC

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03

Received Frank Guilfoyle  
 KANSAS CORPORATION COMMISSION (Technician)  
 Form: District Plugging Report - \_\_\_\_\_  
**MAR 04 2016**  
 CONSERVATION DIVISION