

TB:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-02535-00-00  
Spot: CSWNWNE Sec/Twnshp/Rge: 14-23S-4W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: DOWNIE Well Number: 9  
County: RENO Total Vertical Depth: 3600 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

Conductor Pipe: Size feet: \$117.00  
Surface Casing: Size 16 feet: 274  
Production: Size 7 feet: 3600  
Liner: Size 5.5 feet: 3161

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2001 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 654-8342

Proposed Plugging Method: C.I.B.P. at 2,706'. Top C.I.B.P. with 2 sxs. cement. Perforate casing at 575' & 325'. Run tubing to 575' and spot 50 sxs. cement. Pull tubing to 325' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 11/15/2001 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Placed 2 sxs. cement on top of C.I.B.P. at 2,706'. Pulled tubing. Perforated casing at 575' and 325'. Ran tubing to 575' and spotted 50 sxs. cement w/2% CaCl. Pulled tubing to 523' and spotted 50 sxs. cement w/2% CaCl. W.O.C. Tagged cement at 500'. Ran tubing down 16" x 7" annulus and circulated 150 sxs. cement w/3% CaCl and 200 lbs. hulls to the surface. Ran tubing to 330' and spotted 100 sxs. cement w/5% CaCl and 50 lbs. hulls. W.O.C. Tagged cement at 500'. Ran tubing to 325' and spotted 100 sxs. cement w/5% CaCl and 150 lbs. hulls. W.O.C. Tagged cement at 210'. Ran tubing to 210' and spotted 50 sxs. cement w/5% CaCl. W.O.C. Tagged cement at 210'. Ran tubing to 210' and circulated 50 sxs. cement w/4% CaCl to the surface.

RECEIVED  
KCC DISTRICT #2

NOV 21 2001

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED. INVOICE #3453 & #3454.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-27-01

INV. NO. 2002060987