

9-29 RECEIVED KANSAS CORPORATION COMMISSION

2-010168

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

DEC 12 1997

API NUMBER: 15-15502519-0000

CONSERVATION DIVISION
WICHITA, KS, SECTION 13 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5091 4950 FEET FROM S SECTION LINE
OPERATOR HOWELL OIL COMPANY INC 2970 FEET FROM E SECTION LINE
NAME & ROUTE 1, BOX 22
ADDRESS BURRTON, KS 67020

LEASE NAME: SABIN #1
COUNTY: RENO
WELL TOTAL DEPTH: 3425' 111.31
PIPE:
SURFACE CASING: 12 1/2" @ 225'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 24 MONTH: 9 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: (316) 938-2943

WERE: SAND TO 3265' AND TOP WITH 10 SACKS OF CEMENT. SHOOT PIPE OFF AND PULL SAME. RUN TUBING TO 600' AND SPOT 50 SACKS OF CEMENT. PULL TUBING TO 350' AND CIRCULATE CEMENT TO THE SURFACE. 6 7/8" CASING AT 3415'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON PERFS AT 3317' TO 3325'

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 29 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: RAN TUBING TO 526' AND HIT BRIDGE. WORKED TUBING TO 680' WITH PIPE TONGS AND STOPPED. HOLE WOULDN'T CIRCULATE FLUID. FLUID LEVEL IN HOLE AT 494'. RERAN TUBING TO 777' AND PUMPED 40 SACKS OF GEL, 500 LBS OF HULLS, AND 90 BARRELS OF H₂O; WELL DIDN'T CIRCULATE. PULLED TUBING TO 625' AND SPOTTED 50 SACKS OF CEMENT WITH 4% GEL AND 4% CaCl₂; HOLE DIDN'T CIRCULATE. PULLED TUBING AND WAITED FOR CEMENT TO SET UP. RAN TUBING TO 630' TO TOP OF CEMENT. PULLED TUBING TO 600' AND SPOTTED 50 SACKS OF CEMENT WITH 4% CaCl₂ AND 100 LBS HULLS. HOLE DIDN'T CIRCULATE. PULLED TUBING TO AND CHECKED FLUID LEVEL, FLUID AT 257'. SHOT 6 5/8" CASING AT 465' AND PULLED SAME. RAN TUBING TO 280' AND SPOTTED 275 SACKS OF CEMENT WITH 3% CaCl₂, 400 LBS OF HULLS, AND 100 LBS OF CELOSEAL; HOLE DIDN'T CIRCULATE. PULLED TUBING AND WAITED FOR CEMENT TO SET UP. RAN TUBING TO 310' BUT DIDN'T TAG CEMENT. CIRCULATED 30 BARRELS OF SALTWATER TO THE SURFACE. PULLED TUBING TO 280' AND CIRCULATED 275 SACKS OF CMENT WITH 3% CaCl₂, 500 LBS OF HULLS, AND 100 LBS OF CELOSEAL TO THE SURFACE. RECHECKED HOLE AFTER CEMENT WAS SET UP; CEMENT WAS AT SURFACE.

REMARKS: 60/40 POZ 4% GEL ADDITIVES BY UNITED #4002, #4003, #4005

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
MICHAEL R. WILSON

INVOICED
DATE DEC 12 1997
INV. NO. 49662