

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-28

2-010147

15-155-02520-0000

APT NUMBER: DRILLED 1940

NW NW NE, SECTION 13 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5091 4950 FEET FROM S SECTION LINE
OPERATOR HOWELL OIL COMPANY INC 2310 FEET FROM E SECTION LINE
NAME & R.R. #1, BOX 22
ADDRESS BURRTON, KS 67020

LEASE NAME: SABIN #2
COUNTY: RENO 109.88
WELL TOTAL DEPTH: 3381'
PIPE: _____
SURFACE CASING: 10' @ 256'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 28 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3280' AND CAP WITH 5 SACKS OF CEMENT. PERFORATE PIPE AT 600' AND 300'. RUN 2 3/8" TUBING TO 600' AND SPOT 35 SACKS OF CEMENT. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE.

5 1/2" CASING AT 3330'

OPEN HOLE 3330' TO 3381'

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { X } NONE { _____ }

COMPLETED: HOUR: 14:00 DAY: 28 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3260' AND CAPPED WITH 5 SACKS OF CEMENT. PERFORATED 5 1/2" CASING AT 621' AND AT 310'. RAN 2 3/8" TUBING TO 621' AND SPOTTED 35 SACKS OF CEMENT. PULLED TUBING TO 310' AND CIRCULATED 210 SACKS OF CEMENT TO THE SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED #4816

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 03 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson

MICHAEL R. WILSON

INVOICED

DATE JUN 06 1997

INV. NO. 48234

FORM CP-2/3

REV. 3/90