

6-7

2-010148

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

15-155-02523-0000

API NUMBER: DRILLED 1941

C N/2, SECTION 13 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5091 3960 FEET FROM S SECTION LINE
OPERATOR HOWELL OIL COMPANY INC 2640 FEET FROM E SECTION LINE
NAME & ROUTE 1, BOX 22
ADDRESS BURRTON, KS 67020
LEASE NAME: SABIN #4
COUNTY: RENO
WELL TOTAL DEPTH: 3384' 109.98
PIPE: _____
SURFACE CASING: 8 5/8" @ 250'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 5 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: (316) 938-2943

WERE: SAND TO 3275' AND TOP WITH 5 SACKS OF CEMENT. PERFORATE AT 600' AND 310'. RUN 2" TUBING TO 600' AND SPOT 35 SACKS OF CEMENT. PULL TUBING TO 310' AND CIRCULATE CEMENT TO SURFACE.

5 1/2" CASING AT 3327'

OPEN HOLE AT 3327' TO 3384'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART {} NONE {}

COMPLETED: HOUR: 11:45 DAY: 7 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: RAN 2" TUBING TO 28' AND HIT BRIDGE. RAN 1" TUBING TO 430' AND HIT BRIDGE. RERAN 2" TUBING TO 425' WITH DRILL BIT ON END. DRILLED FROM 425' TO 533'. PERFORATED AT 527' AND SPOTTED 35 SACKS OF CEMENT. PULLED TUBING TO 315', REPERFORATED, AND CIRCUALTED 305 SACKS OF CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED #4814

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

Michael R Wilson
MICHAEL R. WILSON

INVOICED
DATE JUN 25 1997
INV. NO. 48413

JUN 23 1997
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90

DW