

6-2

2-070697

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-21,397-0000

SE SW SE, SECTION 13 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5091 330 FEET FROM S SECTION LINE
OPERATOR HOWELL OIL COMPANY 1650 FEET FROM E SECTION LINE
NAME & RT 1, BOX 22
ADDRESS BURRTON, KS 67020
LEASE NAME: DOLE #3
COUNTY: RENO 118.37
WELL TOTAL DEPTH: 3642'
PIPE: 5 1/2' @ 3393'
SURFACE CASING: 10 3/8" @ 260'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 1:30 DAY: 30 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DARRELL

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: _____

WERE: SAND TO 3220', 5 SACKS
35 SACKS, 600'
310' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 8:30 DAY: 2 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3220' AND 5 SACKS OF COMMON, SHOT 5 1/2" CASING OFF AT 2312'. PULLED TO 600', PUMPED 35 SACKS. PULLED TO 310'. CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED #4815

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

JACK LUTHI

INVOICED
DATE JUN 12 1997
INV. NO. 48335

JUN 10 1997
CONSERVATION DIVISION
WICHITA, KS