

2030288

15-155-07816-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-24-1935

SWNW NW, SEC. 12, T. 23 S, R. 4 (W)

4290' feet from ~~N~~/S section line

4950' feet from ~~E~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5235

Lease Name Newfeldt Well # 2 (SWD)

Operator: Producers Oil Company

County Reno 121.94

Name & Address 711 Philtower Bldg.

Well Total Depth 3752' feet

Tulsa, Ok. 74103

~~Pipe~~ Pipe: Size 7" feet 3614'

Surface Casing: Size 12 1/2" feet 293'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Gressell Oil Field Contractor License Number 5823

Address Box 326 Hayesville, Ks. 67067

Company to plug at: Hour: 09:00 Day: 26 Month: 8 Year: 19 85

Plugging proposal received from Arik Moblack

(company name) Producers Oil Company (phone) _____

were: Perf 3360' to 3390' 4 1/2" eq. lin. to 3024' cent. to surface.

P.B.T.D. 3425' - dropped 2 7/8" cont. lined tub in hole. top of tub 255' from

surface. Fish 2 7/8" tub and plug bottom with 50 ex. cement.

Perf 4 1/2" eq. at 350' and circ. cent. to surface.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00 Day: 28 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT tried to fish tub, could not pull, tried

to pump down 4 1/2" eq. could not at 750" press. Perf. 2 7/8"

tub at 346' to 348' 6 shots. tub plugged at 350' Halliburton

Services # 088006-6 pumped 100 ex. C.P. cement. 3 7/8 cc down 4 1/2" eq.

let set 15 min, pumped 50 ex. cement, let set 15 min, pumped 50 ex, let set 20 min.

pumped 25 ex, let set 40 min, pumped 25 ex. shut well in. Pump loss 275' @ 100"

Remarks: top of well had been cemented, no circulation.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did not) observe this plugging.

DATE SEP 12 1985

INV. NO. 10046

8-28

SEP 12 1985

Signed Don Thompson
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

9-12-85 RO