

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

7-24

API NUMBER: 15-155-21392-0000

165' N OF SE NW, SECTION 23 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5235 3465 FEET FROM S SECTION LINE
OPERATOR PRODUCERS OIL COMPANY 3300 FEET FROM E SECTION LINE
NAME & 427 SOUTH BOSTON, SUITE 711
ADDRESS TULSA, OK 74013

LEASE NAME: VANSICKLE #7
COUNTY: RENO
WELL TOTAL DEPTH: 3669' 119.24
PIPE: _____
SURFACE CASING: 13 3/8" @ 264'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD RECEIVED X

KANSAS CORPORATION COMMISSION

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DUKE DRILLING AUG 06 1996
ADDRESS: 310 WEST CENTRAL, WICHITA, KS 67202 LICENSE: 5929

CONSERVATION DIVISION
WICHITA, KS
1996

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: JOHN ARMBRUSTER

COMPANY NAME: DUKE DRILLING PHONE: (316) 267-1331

WERE: 35 SACKS AT 550'
50 SACKS AT 314'
50 SACKS AT 60'
15 SACKS IN RATHOLE
10 SACKS IN MOUSEHOLE

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { _____ } NONE { X }

COMPLETED: HOUR: 20:30 DAY: 24 MONTH: 7 YEAR: 1996

ACTUAL PLUGGING REPORT: DRILL PIPE WAS RUN OPEN END TO 550' WHERE 35 SACKS OF CEMENT WAS SPOTTED IN PLACE. THE PIPE WAS PULLED TO 314' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 60' WHERE CEMENT WAS CIRCULATED TO SURFACE. THE RATHOLE WAS CIRCULATED WITH 15 SACKS OF CEMENT AND THE MOUSEHOLE WITH 10 SACKS OF CEMENT.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

I DID NOT OBSERVE THIS PLUGGING.

Steve Van Gieson
STEVE VAN GIESON

INVOICED

DATE AUG 08 1996

INV. NO. 46209