

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-16

2-010069

API NUMBER: 15-155-20,187-0001

SW NW NW, SECTION 23 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5235

4000 FEET FROM S SECTION LINE

4950 FEET FROM E SECTION LINE

OPERATOR PRODUCER'S OIL CO

NAME & 427 S BOSTON STE 711

ADDRESS TULSA OK 74103

LEASE NAME: VANSICKLE #6

COUNTY: RENO

WELL TOTAL DEPTH: 3615' 117.49

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 10 1995
CONSERVATION DIVISION
WICHITA, KS

PIPE: _____

SURFACE CASING: 10-3/4" @ 241'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE

ADDRESS: PO BOX 341, CANTON KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 15 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MATT RILEY

COMPANY NAME: PRODUCERS OIL COMPANY PHONE: 405-863-2784

WERE: SET BRIDGE PLUG @ 3270' & TOP OFF W/2 SX CMT - PERF
5-1/2" CSG @ 600' & 375' - RUN TUB TO 600' & SPOT 35 SX
CMT - PULL TUB TO 375' & CIRC CMT TO SURF
5-1/2" CSG @ 3610' - PERFS @ 3284' TO 3610'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 15:30 DAY: 16 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:

SET BRIDGE PLUG @ 327' & TOPPED W/5 SX CMT - PERF
5-1/2" CSG @ 600' & 375' - RAN TUB TO 600' & SPOTTED 40
SX CMT - PULLED TUB TO 375' & TRIED TO CIRC HOLE - NO
CIRCULATION - SPOTTED 177 SX CMT W/NO CIRC - CMT USED
CONTAINED 4% CAL CHLORIDE - RAN 1" TUB INTO 10-3/4" X
5-1/2" ANNULUS - HIT OBSTURCTION @ 250' - CIRC 36 BBLs
WTR & WORKED THROUGH OBSTRUCTION - RAN 1" TO 375' &
CIRC HOLE - CIRC 151 SX CMT TO SURF - RAN 1" TUB DWN
5-1/2" TO 344' - CIRC 40 SX TO SURF - USED 60/40 POZ 4%
GEL - CHECKED PLUG ON 2/17/95 - TOP ODF CMT @ 15' IN
5-1/2" CSG & 30' IN 10-3/4" X 5-1/2" ANNULUS.

REMARKS: USED 60/40 POZ W/4% CACL BY UNITED #1301 & #1302

INVOICED
DID OBSERVE THIS PLUGGING.

DATE MAR 14 1995

INV. NO. 42371

Michael R. Wilson
Michael R. Wilson (AGENT)