

8-9

2-100618

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-155-20,459-0000

NE SE SE , SECTION 23 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5271 990 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR S & K Oil Company
NAME & RR #1, Box 99
ADDRESS Burrtion, KS 67020

LEASE NAME: Blake #11
COUNTY: Reno
WELL TOTAL DEPTH: 3400' PBTB 3381'
PIPE: 5-1/2" @ 3381'
PIPE: 8-5/8" @ 537'/100 sx
SURFACE CASING: 10-3/4" @ 248'/275 sx

110.50

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A
OTHER WELL AS HEREINAFTER INDICATED: 3350-55'

PLUGGING CONTRACTOR: Gressel Oilfield Service
ADDRESS: Box 607, Burrtion, KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 2:00p DAY: 9 MONTH: 8 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Ed Gressel
COMPANY NAME: Gressel Oilfield Services PHONE: 316-463-5161

WERE: Sand 50' over perms or open hole & dum 6 sx cmt
w/bailer - shoot & pull pipe - run tub to 600' - pump
35 sx cmt - pull tub to 300' - circ to surf.

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()
COMPLETED: HOUR: 3:30 DAY: 9 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3275' & dumped 6 sx cmt - shot & pulled
2495' of 5-1/2" - ran tub to 600' & spotted 35 sx cmt -
pulled tub to 300' & circ to surf w/87 sx cmt - fell
110' - refilled with 2 yds slurry mix.

REMARKS: Howco #015702 40/60 total 4% gel Haven Redimix #9819

I DID OBSERVE THIS PLUGGING.

INVOICED

J. L. Sanders
J. L. Sanders (AGENT)

DATE: 8-24-90

INV. NO. 29080

FORM CP-2/3
REV. 3/90

Rec'd 8-17-90
Kee

DL