

2 050277

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-155-02094-0000

SWNWSE, SEC. 23, T 23S, R 4 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5217 5271

Lease Name Blake Well # 10 SWD

Operator: S & K Oil Company

County Reno 162.67

Name & Address 400 S. Boston Bldg.

Well Total Depth 5008 feet

Tulsa, OK 74101

Conductor Pipe: Size 13 3/8 feet 306

Surface Casing: Size 10 3/4 feet 700

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel License Number 5822

Address \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ Day: 30 Month: 7 Year: 19 85

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 7" set at 3830 feet -----cement top to bottom-----put 50 sacks plug on bottom  
and 300' plug at top

Plugging Proposal Received by W (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 Day: 31 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Ran tubing to 3800 feet and spotted 50 sacks of cement. Pulled tubing to 3300 feet. Waited one hour and spotted 50 sacks of cement. Waited one hour spotted 25 sacks of cement, 7 sacks of gel, 3 sacks of hulls. Got circulation Pulled 20 joints of tubing spotted 25 sacks of cement. Pulled all tubing. Filled hole from 280feet to surface with cement with approximately 75 sacks of cement.

Remarks: Allied 146 60/40 pos, 3%cc, 2% gel

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 09 1985

INV. NO. 9508

7-31

RECEIVED STATE CORPORATION COMMISSION Signed A. L. Waef (TECHNICIAN)

AUG 8 1985 8-8-85

RO