

5-27

2-010149

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

R

API NUMBER: 15-095-21,724-0000

C SE, SECTION 6, TOWNSHIP 28, RANGE 6W

OPERATOR LICENSE # 5399 1320 FEET FROM S SECTION LINE
OPERATOR AMERICAN ENERGIES CORPORATION 1320 FEET FROM E SECTION LINE
NAME & ADDRESS 155 NORTH MARKET, SUITE #710
WICHITA, KS 67202

LEASE NAME: GREENLEAF RANCH #5
COUNTY: KINGMAN
WELL TOTAL DEPTH: 3892' 126.49
PIPE:
SURFACE CASING: 8 5/8" @ 219'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A X

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: WHITE & ELLIS DRILLING INC

ADDRESS: P.O. BOX 48848, WICHITA, KS 67202 LICENSE: 5420

COMPANY TO PLUG AT: HOUR: 17:20 DAY: 27 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: ALAN L. DE GOOD

COMPANY NAME: PHONE: (316) 263-5785

WERE: FILL HOLE WITH HEAVY MUD. SPOT PLUGS THRU DRILL PIPE. SPOT 35 SACKS AT 1050', SPOT 35 SACKS AT 600', SPOT 35 SACKS AT 260', SPOT 25 SACKS AT 60', AND FILL RATHOLE WITH 15 SACKS OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { X }

COMPLETED: HOUR: 19:30 DAY: 27 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: FILLED HOLE WITH HEAVY MUD. SPOTTED PLUGS THRU DRILL PIPE. SPOTTED 35 SACKS AT 1050', SPOTTED 35 SACKS AT 600' SPOTTED 35 SACKS AT 260', SPOTTED 25 SACKS AT 60', AND FILLED RATHOLE WITH 15 SACKS.

REMARKS: 60/40 POZ 4% GEL ALLIED #6535

INVOICED

RECEIVED
KANSAS CORPORATION COMMISSION

I DID NOT OBSERVE THIS PLUGGING.

Michael R. Wilson

MICHAEL R. WILSON

DATE 6-24-97
INV. NO. 48397

JUN 23 1997
6-23-97
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3

REV. 3/90

DGW