

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009 - 23454-00-00

SE, Sec. 5, T 16 S, R 13 W/2

330 feet from N/4 section line

330 feet from W/8 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5849

Lease Name Kosar Well # 1

Operator: North Am. Drilg. & Exp.  
Name & Address 3420 10th St.  
Great Bend Ks.

County Barton

Well Total Depth 3435 feet 111.64

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Revlin Drilg. Co. License Number 5671

Address Box 293 Russell Ks.

Company to plug at: Hour: 1 AM Day: 24 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Stan Lindgren

(company name) Revlin Drilg. (phone) 913 483-5355

were: order 170 sk cement 50/50 permix 6% Gel. 3% col. cl.

15x hulls 1- 8 5/8 plug 1- sk. Flow Seal.

Heavy mud between all plugs

Pump cement down drill pipe.

Elev- 1936 Anhydrite 897-922 Arbuckle 3403

Dakota 1725

Signed Dale F. Battagor (TECHNICIAN)

211 = 511

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 AM Day: 24 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3400 for 30 mi.

25 sk @ 3400

25 sk @ 900

100 sk @ 500 mixed with 15x Flow Seal.

1 sk hulls pushed plug to 40'

10 sk @ 40

10 sk in Rat hole.

Remarks:

Cementing to sun.

RECEIVED STATE CORPORATION COMMISSION

APR 30 1984

4-30-84 CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

Signed Dale F. Battagor (TECHNICIAN)

INVOICED

DATE 5-1-84

INV. NO. 1325

4-24