

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,153-0000

LEASE NAME Zenith Waterflood Unit

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #19

SPOT LOCATION 660' North SE, Corner & 2640' West SE Corner

SEC. 14 TWP. 24 RGE. 11 S/2 S/2 (W)

COUNTY Stafford

Date Well Completed 1/29/85

Plugging Commenced 1/29/85

Plugging Completed 1/29/85

LEASE OPERATOR Striker Petroleum Corporation

ADDRESS 5690 DTC Boulevard, Suite 410
 Englewood, Co. 80111

PHONE # (303) 694-3220 OPERATORS LICENSE NO. 8376

Character of Well D & A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? J. H. Metz, Stafford, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Sand		0	110	8 5/8"	110'	None
Shale		110'	252	8 5/8"	142'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug at 600' with 40 sacks of cement. 2nd Plug at 300' with 40 sacks of cement. Top plug at 40' with 10 sacks of cement, 15 sacks in rathole. Plugging completed at 3:15 P. M., January 29, 1985 by State Plugger, J. H. Metz, Stafford, Kansas.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Blackstone Drilling, Inc. License No. 5927
 Address P.O. Box 1184, McPherson, Kansas 67460

STATE OF Colorado COUNTY OF Arapahoe RECEIVED
 STATE CORPORATION COMMISSION

Striker Petroleum Corporation (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: FEB 21 1985
 I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. 2-21-85
 STRIKER PETROLEUM CORPORATION
 Wichita, Kansas

(Signature) BY: [Signature]

(Address) 5690 DTC Boulevard, Suite 410
 Englewood, Co. 80111

SUBSCRIBED AND SWORN TO before me this 21 day of February, 1985

Nancy J. McMay
 Notary Public

My Commission expires: March 1, 1986

NANCY J. McMAY
 5000-E So. Pagosa St.
 Aurora, CO 80015

Form CP-4 1-84
 Revised 06-83



15-185-22153-0000

Blackstone Drilling, Inc.

Box 1184 • 529 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460
January 30, 1985

COMPANY: STRIKER PETROLEUM CORPORATION
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: ZENITH WATERFLOOD UNIT #19
 LOCATION: 660' North SE Corner & 2640' West SE corner of S/2 S/2 Section 14-24-11W, Stafford County, Kansas
 COMMENCED: January 22, 1985
 COMPLETED: January 29, 1985
 ELEVATION

0	to	110	Sand
110	to	1535	Shale
1535	to	2190	Shale & Lime
2190	to	2870	Lime & Shale
2870	to	3083	Shale & Lime
3083	to	3234	Lime
3234	to	3395	Lime & Shale
3395	to	3435	Lime
3435	to	3540	Lime & Shale
3540	to	3628	Lime
3628	to	3810	Lime & Shale
3810	to	3924	Lime
		3924	T. D.

Cut 12 1/4" hole to 250' and run 252' of 8 5/8" casing, cemented with 175 sacks of cement at 250'. Plug down at 6:00 P. M., January 22, 1985. Hole dry and abandoned. Set bottom plug at 600' with 40 sacks of cement. Set second plug at 300' with 40 sacks of cement. Top plug at 40' with 10 sacks of cement., 15 sacks in rathole. Plugging completed at 3:15 P. M., January 29, 1985 by State Plugger, J. H. Metz, Stafford, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

TOPS:

FEB 21 1985

Measurements taken from K. B.

CONSERVATION DIVISION
Wichita, Kansas
CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Zenith Waterflood Unit #19, located on the 660' North SE Corner and 2640' West SE Corner of S/2 S/2 Section 14-24-11W, Stafford County, Kansas.

P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 30th day of January, 1985.

Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT
McPherson County, Kansas
My Appt. Exp. June 23, 1985