

15-095-19127-000

Form CP-3
Rev. 6-26-62

KS
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Martin & Kellar

Complete Address: 713 Kennedy Bldg., Tulsa, Oklahoma

Lease Name Harding Well No. # 1

Location C W/2-NE Sec. 1 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 1767

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling Inc.

Address: 905 Wichita
~~912 Central Bldg., Wichita, Kansas~~ License No.

Operation Completed: Hour 4:00AM Day 21st Month Dec. Year 1964

The Above well was plugged as follows:

218' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 215', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 215', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 12/23/64
INV. NO. 383-W

Signed: Archie Elving
Well Plugging Supervisor