

15095-01858000

Form CP-3
Rev. 6-26-62

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
issued February 21, 1968.

Operator's Full Name Martin & Keller

Complete Address: 1430 Terrace, Tulsa, Oklahoma 74104

Lease Name Casley Well No. # 1

Location SW NE SW Sec. 1 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 1700'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 10:30AM Day 28th Month February Year 1968

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cemented with 150 sacks. 1689' of 5 1/2" long
string, cemented with 50 sacks. This is an open hole. Bottom of the hole
was sanded to 1650', and cemented with 5 sacks, through the dump bailer, with
cement from 1650' to 1610'. 1150' of 5 1/2" long string was recovered from the
hole. Hole was filled with mud to 200', rock bridge from 200' to 190', and
cemented with 25 sacks, with cement from 190' to 115'. Hole was filled with
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with
cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/5/68
INV. NO. 1361-W