

15-095-01033-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 17 1965  
06-17-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name McAdams Pipe & Supply Company

Complete Address: P. O. Drawer 960, Bristow, Oklahoma

Lease Name Richey Well No. # 1

Location SE SW SE Sec. 2 Twp. 28 Rge. 5 (E) W

County Kingman Total Depth 3814'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 2:30 PM Day 16th Month June Year 1965

The Above well was plugged as follows:

163' of 8 5/8" surface pipe, cemented with 150 sacks. 3814' of 5 1/2" long  
string, cemented with 100 sacks. Top perferation 3773'. Bottom of the hole  
was sanded to 3760', and cemented with 5 sacks. 3019' of 5 1/2" long string  
was recovered from the hole. Hole was filled with mud to 200', and 10' of  
rock bridge, and cemented with 30 sacks, bringing the top of the cement to  
153' in the surface pipe. Hole was filled with mud to 40', and 10' of rock  
bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/17/65

INV. NO. 1325-W