

15095-015470500

NORTH

**Locate well correctly on above
Section Plat**

State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above Section Plat

County. Sec. 27 Twp. 28 Rge. (E) 5 (W) Kingman

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW

Lease Owner Earl F. Wakefield

Lease Name A. Bolinger Well No. 1

Office Address 307 Union Natl. Bk. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 8 19 51

Application for plugging filed November 9 19 51

Application for plugging approved November 9 19 51

Plugging commenced November 9 19 51

Plugging completed November 9 19 51

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... Ruel Durkee

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3895 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to feet for each plug set.

Filled with heavy mud from 3895 to 130 feet, Bridged with wood plug, Hulls & Hull Sacks at 130 feet cemented with 15 sacks. Filled with heavy mud to 15' from Bottom of Cellar. Bridged with wood plug, hulls and hull sacks cemented with 5 sacks to bottom of Cellar. Welded steel cap on surface.

RECEIVED
STATE DEPT
NOV 20 1951
COMMUNICATIONS SECTION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Earl F. Wakefield

Address 307 Union National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl E. Wakefield (~~employee of owner~~) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. and F. W. Ackfeld
307 Union Natl. Bk. Bldg., Wichita, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November 1951

My commission expires 12-23-54

28-5091-g

8-50-10M

FILE NO. 27-18-5W
BOOK PAGE 180 LINE 12

15-09501547-0000

A. Bolinger #1
 Owner: Earl F. Wakefield, et al
 Contractor: Earl F. Wakefield
 Comm: 10-28-51 Comp: 11-8-51

NW NW NW 27-28-5
 Kingman County, Kansas
 Casing: 131' of 8 5/8"

Elevation 1384'

Surface	125
Shale & Lime	574
Shale & Shells	985
Lime & Shale	1090
Lime	1250
Lime & Shale	1995
Shale & Lime	2050
Lime & Shale	2100
Lime	2205
Sand	2220
Lime	2303
Lime & Shale	3270
Lime	3403
Sand	3429
Lime	3475
Lime & Shale	3713
Lime	3725
Lime & Shale	3787
Shale	3834
Mississippi Lime	3895
Lime Total Depth	3895

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct
 copy of the log on the A. Bolinger #1 well located NW NW NW
 27-28-5, Kingman County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 20 day of Nov, 1951.

James J. Gentry

My Commission Expires: 12-23-54

RECEIVED
 NOV 20 1951
 CONSERVATION DIVISION
 WICHITA, KANSAS

FILE SEC-271-1-R-SW
 BOOK PAGE 12 LINE 24