


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 28 Twp. 28 Rge. (E) 5 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SE SE NE
Lease Owner Earl F. Wakefield, et al
Lease Name Bolinger Well No. 1
Office Address 307 Union Natl. Bk., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 7 19 50
Application for plugging filed October 7 19 50
Application for plugging approved October 7 19 50
Plugging commenced October 7 19 50
Plugging completed October 7 19 50
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas.
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	129.70'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Filled hole with heavy mud to 140 feet.
Pushed plug to 140 feet and set with 15 sacks of cement. Filled hole to 30 feet of surface.
Placed plug at 30 feet and cemented with 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Earl F. Wakefield
Address 307 Union Natl. Bk.
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. M. Callaway (employee of owner) or ~~owner or operator~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. M. Callaway*
307 Union National Bank (Address)

SUBSCRIBED AND SWORN to before me this 13th day of October, 19 50

My commission expires 12-23-50

28-3278-S 4-50-10M

PLUGGING
FILE SEC 28 T 28 R 22
BACK PAGE 33 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1950
15-095-00219-0000
CONSERVATION DIV.
Wichita, Ks.

Bolinger #1
OWNER: Earl F. Wakefield, et al
CONTRACTOR: Earl F. Wakefield
COMM: 9-25-50 COMP: 10-7-50

C SE SE NE 28-28S-5W
Kingman County, Kansas
CASING: 129.70' of 8 5/8"
set @ 140' w/100' sax

Elevation: 1387 DF

Surface Clay	30
Lime & Shale	140
Shale & Shells	200
Shale, salt & shells	700
Lime shells & shale	830
Shale, Shells & Lime	1090
Lime & Shale	1585
Sandy Lime & Shale	1765
Lime & Shale	1790
Shale	1865
Lime & Shale	2310
Shale & Shells	2510
Shale & Lime	3830
Lime	3885
T. D.	3885

Geological Tops:
Mississippi 3826

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)


I hereby certify that the above is a true and correct copy
of the log of the Bolinger #1 well located C SE SE NE 28-28S-5W,
Kingman County, Kansas.

Tom Cuccarone

Subscribed and sworn to before me this 16th day of October, 1950.

E. James Gaffney
Notary Public

My Commission Expires: 12-23-50



RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1950
CONSERVATION DIV.
Wichita, K.