


15-095-01321-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County, Sec. 28 Twp. 28 Rge. (E) 5 (W)

Location as "NE/CNW%SW%" or footage from lines NE/4 NW/4
Lease Owner Earl F. Wakefield & C. I. Ross
Lease Name Bolinger "A" Well No. 3
Office Address 515 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 11 19 63
Application for plugging filed December 11 19 63
Application for plugging approved December 16 19 63
Plugging commenced December 11 19 63
Plugging completed December 11 19 63
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving Box 248 Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	149'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 250 feet with heavy mud and bridged with two sacks hulls
Cemented with 30 sacks to 125 feet. Checked with wire line measure.
Filled with heavy mud to 35' and bridged with one sack hulls and cemented
to bottom of cellar with ten sacks. Plugged rathole with three sacks.

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1963
12-24-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Earl F. Wakefield (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Building, Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 63

My commission expires January 25, 1965
Wanda W. Riley Notary Public.

LEASE: BOLINGER "A" NO. 3
OWNER: EARL F. WAKEFIELD AND
C. I. ROSS
CONTRACTOR: EARL F. WAKEFIELD
CON: 12-3-63
COMP: 12-11-63

LOCATION: NE NW
SECTION 28-28-5W
KINGMAN COUNTY, KANSAS
CASING: 8 5/8" Set at 149'

Blue and Red Keel	149
Shale and Shells	355
Shale & Shells and Anhydrite	1055
Shale and Shells	1245
Lime and Shale	1420
Lime and Anhydrite	1570
Lime and Shale	1915
Shale and Lime	2167
Lime and Shale	2460
Lime and Shale	2760
Shale and Lime	2980
Lime	3092
Lime and Shale	3265
Lime	3545
Lime and Shale	3872
Lime	3890
R.T.D.	3890

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1963
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the BOLINGER "A" NO. 3 well, located NE/4 NW/4 Section 28-28-5W, Kingman County, Kansas.

EARL F. WAKEFIELD
BY Fred S. Kessler

Subscribed and sworn to before me this 23rd day of December, 1963.

My commission expires:
January 25, 1965

Wanda W. Riley
WANDA W. RILEY NOTARY