

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

XXXFORMATION PLUGGING RECORDXXX

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

A 4x4 grid with a dot at the intersection of the third column and the second row from the bottom.

**Locate well correctly on above
Section Plat**

Reno County. Sec. 26 Twp. 23S Rge. (E) 4. (W) 4

Location as "NE¼NW¼SW¼" or footage from lines. 50' west of center of SE/4

Lease Owner. Sinclair Prairie Oil Co.

Lease Name. Adam T Base Well No. 1-500

Office Address. Box 521, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Shallow disposal well

Date well completed. April 5 1935

Application for plugging filed. Aug 20 1947

Application for plugging approved. Aug 21 1947

Plugging commenced. Aug 4 1948

Plugging completed. Aug 11 1948

Reason for abandonment of well or producing formation. not in use, not needed.

If a producing well is abandoned, date of last production.....-.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes.....

Name of Conservation Agent who supervised plugging of this well.....Ruel Durkee.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....550Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

550' - 35' mud
35 - 0 cmt 8 sx

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Mr E.H. Gibbons.....
Address.....~~Box 521X~~ Box 774, Great Bend, Kas

STATE OF Kansas, COUNTY OF Barton, ss.
I, E. H. Gibbons (employee of owner) or ~~owner or operator~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 774 Great Bend, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 18 day of August, 1948

My commission expires.....April 10, 1950.....

.....
Notary Public.

21-6858-RS

2-47—GMI

PLUGGING
FILE SEC 26-T-23R 40
BOOK PAGE 127 LINE 18

Well Log
Sinclair Prairie Oil Co

Adam Base
26-23S-4W Reno Co.
Shallow Disposal Well
SE/4, 50' west of center.

Drilling Begun 3/20/35
Completed 4/5/ 1935
Top of Mica or Salt 443'
TD 550'
12½" csg @ 131'
10" " @ 254'
8¼" " @ 408

Surface Soils	8
Sand & Gravel	12
Clay	20
Sand & Gravel	38
Sandy Mud & Gravel	95
Sand-Clay	120
Sandy Mud & Clay	160
Shale-blue	280
Shell,hard	285
Shale,blue hard	410
Shale,gray	445
Mica-Salt 200' salt wtr	451
Shale-Lime-Shells	461
Lime-Shale	477
Shale & Shells	488
Anhydrite	499
Shale-blue	502
Shells	504
Gray Shale & Shells	550'TD

PLUGGING
FILE SEC 26 T 23 R 4W
BOOK PAGE 127 LINE 18