

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado, Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-155-20747-0000

API NUMBER April 15, 81

LEASE NAME Loyd Hookinson

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 0-SWSE-SW TWP. 23 RGE. 4W (E) or (W)

COUNTY 3 Reno

LEASE OPERATOR Excalibur Prod Co Inc

ADDRESS 523 W. Kansas Box 278 McPherson

PHONE (316) 241-1265 OPERATORS LICENSE NO. 5330

Date Well Completed 4-81

Character of Well Oil

Plugging Commenced 9-9-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-18-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached?         

Producing Formation Miss Depth to Top 3352 Bottom          T.D. 3360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<del>7/8</del> 5/2	265' 3352	0 2388

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back w/ sand to 3300 Dump 5 sacks cement w/ Dump bailer  
shot off pipe. Build bridge @ 350' Fill to surface w/ A-di-Mix  
Cap well off

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Serv Inc License No. 3004

Address Box 607 Burton KS 67020

STATE OF KS COUNTY OF Harvey, ss.

Ed Gressel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ed Gressel

(Address) Box 607 Burton KS 67020

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of September, 19 86

Mary H. Klein  
Notary Public

My Commission Expires: March 15, 1986



9-23-86

Form CP-4  
Revised 08-84

SEP 23 1986



**Blackstone Drilling, Inc.**

Box 1184 • 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

April 7, 1981

COMPANY: CHARLES D. JOHNSON  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: *Gleng* BOSKINSON #1  
 LOCATION: C SW SE SW Section 33-23-4W,  
 Reno County, Kansas  
 COMMENCED: March 24, 1981  
 COMPLETED: April 5, 1981  
 ELEVATION:

0	to	240	Sand
240	to	630	Shale
630	to	1010	Shale & Lime
1010	to	1333	Lime & Shale
1333	to	2278	Shale & Lime
2278	to	2300	Lime
2300	to	2615	Shale & Lime
2615	to	2850	Lime & Shale
2850	to	3060	Shale & Lime
3060	to	3195	Lime & Shale
3195	to	3273	Shale & Lime
3273	to	3324	Lime
3324	to	3356	Mississippi
		3356	T. D.

Cut 17" hole to 263' and run 265' of 10 3/4" surface casing, cemented with 200 sacks of cement at 263'. Plug down at 2:15 P. M., March 24, 1981. Run 3362' of 5 1/2" casing, cement 4 foot off bottois with 75 sacks of cement at 3352'. Plug down at 5:45 A. M., April 6, 1981.

TOPS: MISSISSIPPI - 3324'

Measurements taken from K. B.

**CERTIFICATE**

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of the log on your Hoskinson, located on the C SW SE SW Section 33-23-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*P. E. Plouffe*  
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 7th day of April, 1981.

*Johnnie L. Schmidt*  
 Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT
McPherson County, Kansas
My Appt. Exp. June 23, 1981