


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-55-20044-0000



Locate well correctly on above Section Plat

Reno --- County, Sec. 33 Twp. 23 Rge. 4 (E) --- (W)
Location as "NE/CNW/SW" or footage from lines --- C/NE -SE ---
Lease Owner Sterling Drilling Company
Lease Name Geering Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19__
Application for plugging filed _____ 19__
Application for plugging approved _____ 19__
Plugging commenced 7/16/68 _____ 19__
Plugging completed 7/17/68 _____ 19__
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3418 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	248'	none
				8-5/8"	586'	142'
				5 1/2"	3410'	2933'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3350' and set 5 sacks of cement.
Loaded hole, shot pipe at 2945', pulled 90 joints. Cut 8-5/8"
loose and pulled 142'. Bailed hole to 235', set rock bridge to
225' and plugged with three yards of ready mix.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being duly sworn, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.

(Signature) Paul Knight
Chase, Kansas
(Address)

Subscribed and sworn to before me this 18th day of July, 19 68



Margaret Melcher
Notary Public.

My commission expires February 15, 1971

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1968
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
Sterling, Kansas 67579

15-155-26044-0000

WELL LOG ----- GOERING #1
LOCATED: NE SE Section 33-23S-4W, Reno County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 3, 1968
COMPLETED: January 11, 1968

ROTARY TOTAL DEPTH: 3418'

LOG

0 - 170	Sand and Shale
170 - 255	Shale and Lime Shell
255 - 550	Shale
550 - 590	Dry Drill
590 - 1065	Shale and Lime
1065 - 1500	Shale
1500 - 1935	Shale and Lime
1935 - 2220	Shale
2220 - 2546	Lime and Shale
2546 - 2947	Lime
2947 - 3360	Shale and Lime
3360 - 3418	Chert and Lime

CASING RECORD

Ran 12 Jts. 10" casing, 249.22', threads off, set at 248' with 275 cubic feet 60-40 Pozmix with HA5. Plug down at 6:30 AM, 1-4-68.

Ran 18 Jts. 8 5/8" 2 1/2" J-55 8rd casing 586.86' threads off set @ 586' KB with 100 cubic feet HA5 60/40 Pozmix. Plug down 7:00 AM 1-5-68. Halliburton Type M Casing Shoe. Bottom 4 jts. has collars spotted by welder.

Ran 105 Jts., 3400.91', threads off, 5 1/2" 1 1/2" J-55 8rd casing, set at 3410' with 100 cubic feet saltsaturated Pozmix cement. K.B. is 10' above spider. Shoe joint 28.15'. Plug down at 5:00 PM, 1-11-68.