

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-155 20, 803-0000 R

SE, Sec. 5, T 24 S, R. 40 W E

C N/2 feet from N/S section line

S/2 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5330

Lease Name Teten Well # 3 R

Operator: Escalibur Prod. Co. Inc.

County Reno

Name & Address 523 W. Kansas

Well Total Depth 3368 feet

McPherson, Ks. 67460

Condenser Pipe: Size 5 1/2" feet 3364'

Surface Casing: Size 8 7/8" feet 285'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor H + H. Csg. Pulling License Number 6053

Address 1427 N. Halstead, Hutchinson, Ks. 67501 Log. 558

Company to plug at: Hour: 11:00 AM Day: 15 Month: 2 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Ron Hurst

(company name) H. + H. Csg. Pulling (phone)

were: Sand to 3300' dump. 6 sq. cont.

pump. 15 gal. 6 sq. hullo, 10 sq. gel. submer. plug. 100 sq. cont.

Signed Maurice Leslie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00 P.M. Day: 15 Month: 2 Year: 1983

ACTUAL PLUGGING REPORT Sanded hole to 3300', dumped 6 sq. cont. trailer

shot + pulled 2500' 5 1/2" csg. Allied Cementing # 34250

pumped. 15 sq. gel., 6 sq. hullo, 10 sq. gel., 100 sq. cont. 3% cc

down 8 7/8" csg. Pump. Press 500# S.I.P. 200#

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 22 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Ron Thompson  
(TECHNICIAN)

INVOICED

DATE MAR 24 1983

INV. NO.

36784

FORM CP-2/3  
Rev. 9-82

Phone 463-2605

# Burrton Lumber & Development, Inc.

LUMBER - BUILDERS' SUPPLIES - HARDWARE

BURRTON, KANSAS 67020

Customer's

Order No.

Date

19

Name

Address

SOLD BY

CASH

C.O.D.

CHARGE

ON  
ACCT.

MDSE.  
RETD.

PAID  
OUT

QUAN.

DESCRIPTION

PRICE

AMOUNT

TAX

TOTAL

All claims and returned goods MUST be accompanied by this bill.

18076

Rec'd by