

2100501

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 9-3-83
SW, SEC. 5, T 24 S, R 4 W/EX

TECHNICIAN'S PLUGGING REPORT

330 feet from N/S section line
3960 feet from W/E section line

Operator License # 5330

Lease Name Moretha Miller Well # 2

Operator: Excalibur Production Co., Inc.
Name & Address: Box 278
McPherson, KS 67460
316-241-1265

County Reno 109.59
Well Total Depth 3372 feet
Conductor Pipe: Size 5-1/2 feet 3367
Surface Casing: Size 12-3/4 feet 302 235 SX

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated O.H. 3367'-72'

Plugging Contractor Gressel Oilfield Serv License Number 3004

Address Box 607, Burrton, KS 67020

Company to plug at: Hour: 1:00 Day: 26 Month: 5 Year: 19 89

Plugging proposal received from George Rail

(company name) Gressel Oilfield Serv (phone) _____

were: Dump sand to 3310' - w/6 sx cement - shoot & pull pipe - spot 35 sx cement at 700' thru tubing - then 50 sx cement at 350' - then fill to surface from 60'

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 Day: 26 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT Dump sand to 3310' w/6 sx cement - shot & pulled 827' of 5-1/2" tubing to 700' & spotted 35 sx cement - pulled pipe to 350' & spotted 50 sx cement - pulled pipe to 60' & circulated cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

JUN 15 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: HOWCO #796075-5 60/40 4% gel
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-20-89
INV. NO. 25085

observe this plugging.
WK

Signed J.C. Sanders
(TECHNICIAN)

6-15-89