

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

12-14

API NUMBER: 15-155-20,143-0000

SW-SE-SE SECTION 5 TOWNSHIP 24S RANGE 4W

OPERATOR LICENSE # 5330 330 FEET FROM S SECTION LINE  
OPERATOR Excalibur Production Co.Inc 990 FEET FROM E SECTION LINE

NAME & P.O. Box 278  
ADDRESS McPherson, KS 67460

LEASE NAME: Teten # 2  
COUNTY: Reno 109.59  
WELL TOTAL DEPTH: 3372'  
PIPE: \_\_\_\_\_  
SURFACE CASING: 10 3/4" @ 312'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Quality Well Service Inc.  
ADDRESS: 249 Beth Drive Sterling, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 0:900 DAY: 14 MONTH: 12 YR: 1998

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service Inc. PHONE: 316-727-3410

WERE: Sand to 3280' and top with five sacks of cement. Shoot pipe off and pull same. Run 2 3/8" tubing to 650' and spot thirty-five sacks of cement. Pull tubing to 375' and circulate cement to the surface. Perforations- 3327 to 3372. 5 1/2" casing at 3366'.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 11:00 DAY: 14 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT: Sanded to 3190' and topped with five sacks of cement. Shot pipe off at \_\_\_\_\_ And pulled same. Ran 2 3/8" tubing to 651' and spotted thirty-five sacks of cement. Pulled tubing to 372' and circulated two hundred and forty sacks of cement to the surface. Cement fill to 90' below surface. Topped with thirty sacks of cement. This was on 12-15-98.

REMARKS: Used 60/40 pos mix with 4% gel by United. Invoice # 5270

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Mike Wilson

*Rec'd  
1-15-99  
M4*

1-22-99  
60556