

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-15

API NUMBER: 15-155-20,091-0000

E/2-SE-SE SECTION 5 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 5330
OPERATOR Excalibur Production Co.Inc.
NAME & P.O. Box 278
ADDRESS McPherson, KS 67460

660 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE
LEASE NAME: Teten # 1
COUNTY: Reno
WELL TOTAL DEPTH: 3360' 109.20
PIPE: _____
SURFACE CASING: 10 3/4" @ 303'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____
RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR: Quality Well Service Inc.
ADDRESS: 249 Beth Drive Sterling, KS 67579 LICENSE: 31925

JAN 11 1999

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 15 MONTH: 12 YR: 1998

CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service Inc. PHONE: 316-727-3410
WERE: Sand to 3285 and top with five sacks of cement. Shoot pipe off and pull same. Run 2 3/8" tubing to 650' and spot thirty-five sacks cement. Pull tubing to 375' and circulate cement to the surface. Perforations-3335 to 3360. 5 1/2" casing at 3360.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 15:00 DAY: 15 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT: Sanded to 3280' and topped with five sacks of cement. Shot pipe off at 2205;. Pulled pipe to 650' and spotted thirty-five sacks cement. Pulled pipe to 352', and circulated thw hundred and ten sacks of cement to the surface. Retrieved 2205' of 5 1/2" casing (68 jts).

REMARKS: Used 60/40 pos mix with 4% gel by United. Invoice # 5251

I DID OBSERVE THIS PLUGGING.
Michael R. Wilson
MICHAEL R. WILSON

60552