

2-010054

8-23

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-20,627 D-22,212
E2 SE NW, SECTION 4 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 5357 3300 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR FRANK J BLACK OIL OPER
NAME & 11609 REEDER
ADDRESS OVERLAND PARK KS 66210

LEASE NAME: GILBERT 1B
COUNTY: RENO
WELL TOTAL DEPTH: 3355' 109.04

CONDUCTOR PIPE: _____

SURFACE CASING: 12-3/4" @ 288'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: D&R WELL SERVICE
ADDRESS: RR 4 BOX 36 GALVA KS LICENSE: 4873

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 22 MONTH: 8 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: KERMIT SCHMIDT
COMPANY NAME: SCHMIDT OIL CO PHONE: 316-241-1255

WERE: SHOOT OFF 5-1/2" CSG @ 1700' - PULL 1 JT CSG - RUN TUB
TO TOP OF FISH & SPOT 35 SX CMT - PULL TUB - PULL CSG
TO 600' & SPOT 35 SX CMT - PULL CSG TO 326' & CIRC CMT
TO SURF

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 09:30 DAY: 23 MONTH: 8 YEAR: 1994

ACTUAL PLUGGING REPORT:
SHOT OFF 5-1/2" CSG @ 1517' - RAN TUB TO 1520' &
SPOTTED 35 SX CMT - PULLED TUB - PULLED CSG TO 609' &
SPOTTED 35 SX CMT - PULLED CSG TO 310' & CIRC 205 SX
CMT TO SURF - CHECKED TOP PLUG @ 14:30 - CMT 8' BELOW
SURFACE - RETRIEVED 1517' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ 4% GEL BY ALLIED #1570

I DID OBSERVE THIS PLUGGING.

INVOICED
SEP 12 1994

Michael R. Wilson
Michael R. Wilson (AGENT)

DATE _____
INV. NO. 41185
8-23

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 06 1994
CONSERVATION DIVISION
WICHITA, KS