

1-3

15-155-02904-0000

RECEIVED
KANSAS CORPORATION COMMISSION

2-

JAN 14 1994

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 1-28-1938

C SW SE, SECTION 4 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 5235 660 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR PRODUCERS OIL CO
NAME & 427 S BOSTON, STE 711
ADDRESS TULSA, OK 74103-4199

LEASE NAME: WELCH 1-B
COUNTY: RENO
WELL TOTAL DEPTH: 3372' 109.59

PIPE: _____

SURFACE CASING: 12-1/2" @ 306'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE
ADDRESS: P O BOX 341, CANTON, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 10:00A DAY: 3 MONTH: 1 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: RICHARD KNOBLOCK
COMPANY NAME: PRODUCERS OIL PHONE: 918-582-1188

WERE: RUN TUBING TO 3200' & SPOT 35 SX CMT - PERF 7" CSG @
600' & SPOT 35 SX THRU TUB - PULL TUB TO 400' & CIRC
CMT TO SURF - RUN 1" TUB DWN 12-1/2" & 7" ANNULUS TO
350' & CIRC CMT TO SURF. 7" CSG 3309' - OH 3309-3372'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 15:15 DAY: 3 MONTH: 1 YEAR: 1994

ACTUAL PLUGGING REPORT:
RAN TUB TO 3200' & SPOTTED 35 SX CMT - PERF 7" CSG
@ 600' & SPOTTED 35 SX CMT THROUGH TUB - PULLED TUB
TO 400' & CIRC CMT TO SURF - RAN 1" TUB TO 350' & CIRC
CMT TO SURF - USED 306 SX CMT ON TOP PLUG

REMARKS: USED 60/40 POZ 2% GEL - UNITED #4728

I DID OBSERVE THIS PLUGGING.

INVOICED

FEB 04 1994

DATE _____

M

MICHAEL R. WILSON (AGENT)

INV. NO. 39856