

15-155-19198-0001

10-29

2-100785

138  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: March 21, 1938

NE SE, SECTION 4 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 5235 1980 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

OPERATOR Producer Oil Company  
NAME & 427 S Boston Ave, #711  
ADDRESS Tulsa, OK 74103-4199

LEASE NAME: Welch #2-B

COUNTY: Reno  
WELL TOTAL DEPTH: 3382' 109.92

PIPE: 7" @ 3299'/125 sx  
SURFACE CASING: 12-1/2" @ 275'/275 sx

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Sunflower Well Service  
ADDRESS: P. O. Box 341, Canton, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 29 MONTH: 10 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Bud Davis  
COMPANY NAME: Sunflower Well Service PHONE: 316-638-4723

WERE: Sand 50' into long string w/10 sx cmt - perf 680'  
575' & pump 50 sx cmt - run 1" to 325' & circ outside 7"  
outside 7"

NOV 10 1992

PLUGGING PROPOSAL RECEIVED BY: District Office  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 4:15p DAY: 29 MONTH: 10 YEAR: 1992

ACTUAL PLUGGING REPORT:  
Sanded to 3249' & dumped 10 sx cmt w/bailer - perf  
@ 580' & pumped 50 sx cmt - ran 1" to 325' & circ in  
annulus w/210 sx cmt - ran 1" to 325' inside 7" &  
pumped 70 sx cmt - circ.

REMARKS: Howco #298929

I DID OBSERVE THIS PLUGGING.

J. L. Sanders  
J. L. Sanders (AGENT)

**INVOICED**  
DATE 12-04-92  
INV. NO. 36952

10-29-92 JAN 22 1993