

2-100645

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 11/18/66

NW SE SW, SECTION 4 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 4767 FEET FROM S SECTION LINE _____
FEET FROM E SECTION LINE _____

OPERATOR Ritchie Exploration, Inc.
NAME & 125 North Market, #1000
ADDRESS Wichita, KS 67202

LEASE NAME: Lake "p" #2
COUNTY: Reno
WELL TOTAL DEPTH: 3347'

108.77

PIPE: 13-3/8" @ 153'/150 SX
SURFACE CASING: 8-5/8" @ 541'/350 SX
SURFACE CASING: 5-1/2" @ 3342'/65 SX

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: open hole Miss.

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: 13 MONTH: 11 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Doyle Kelso
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 3290' w/5 sx cmt - shoot & pull pipe to 800'
- spot 25 sx cmt, then 50 sx at 650' - circ to surf
from 250'.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

11-16-90

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)
COMPLETED: HOUR: _____ DAY: 14 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3278' & dumped 6 sx cmt w/bailer - shot 5 -
1/2" pipe at 2300' & pulled to 800' & pumped 25 sx cmt
- pulled pipe to 650' and spotted 50 sx cmt - pulled
pipe to 266' and circ cmt to surf - topped off.

NOV 16 1990
CONSERVATION DIVISION
Wichita, Kansas

REMARKS: Allied #6032

I DID OBSERVE THIS PLUGGING.

INVOICED

John Sanders
John Sanders (AGENT)

DATE NOV 20 1990
INV. NO. 30016

RECEIVED
NOV 16 1990

15-155-30153-0000

STATE		Kansas	
COUNTY	FARM	COMPANY	WELL NO.
Reno		Wofford Oil Co.	#2
BLOCK	SURVEY		
	NW SE SW		
SECTION		3347' BTD	
4		TOTAL DEPTH	
T	R		
245.	4W.		
		CONTRACTOR	Wofford Drlg. Co.
		COMMENCED	Nov. 9, 1966
		COMPLETED	Nov. 17, 1966
		REMARKS	
ALTITUDE		1477' ±	
PRODUCTION			

CASING RECORD		
SHOT	QUARTS	BETWEEN
		13 3/8" @ 153' w/ 150 SX
		8 3/8" @ 541' w/ 250 SX
		5 1/2" @ 3347' w/ 65 SX
TIME RATE SCALE: 1/10" =		MINUTES

