

* Correction

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-21673-00-00
Spot: NWSEW Sec/Twnshp/Rge: 2-18S-13W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TINDALL Well #: 5
County: BARTON Total Vertical Depth: 3446 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3371		150 SX
SURF	8	419		275 SX

Well Type: SWD UIC Docket No: D19730.0 Date/Time to Plug: 02/16/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method:

Ordered 13 sx gel, 450 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Well was sanded off to 2925'. Operator was going to pull casing and decided to plug through tubing.
Perforated at 1400', 750' and 450'. Ran tubing to 2900' and pumped 13 sx gel followed by 25 sx cement w/50 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface on casing w/85 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe w/90 sx cement.

GPS: 38.51762 -098.73266

Perfs:

Top	Bot	Thru	Comments
3371	3446		

Remarks: QUALITY

Plugged through: TBG

District: 04

Signed

Bruce Rodie / ap
(TECHNICIAN)