

5060133

10-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-21,232-00-00

NW NW SW, SEC. 9, T. 18 S, R. 10 WXX
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Cody-Habiger Well # 3

Operator: John J. Darrah, Jr.

County Rice 107.25

Name & Address 412 E. Douglas, #1

Well Total Depth 3300 feet

Wichita, KS 67202

XXXXXXXXX Pipe: Size 4-1/2" feet 3297/150sx

Surface Casing: Size 8-5/8" feet 266

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Eng. Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: am Day: 7 Month: 10 Year: 1988

Plugging proposal received from Joe Foelgner, Jr.

(company name) John J. Darrah, Jr. (phone)

were: Sand to 3065' and cap with 4 sx - pump 4 sx hulls, 25 sx gel, 1 sx hulls
and 125 sx 60/40 poz 2% gel.

Plugging Proposal Received by District #2
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00a Day: 7 Month: 10 Year: 1988

ACTUAL PLUGGING REPORT Sanded to 3065' and capped with 4 sx cement - pumped
4 sx hulls, 25 sx gel, 1 sx hulls and 125 sx 60/40 poz 2% gel.

Perf: 3116-20'

PBTD 3251'

Max Press 650#. Shut in Pressure 450#. Rec. 2390' of 4-1/2" CONSERVATION DIVISION

Remarks: HOWCO #763014
(if additional description is necessary, use BACK of this form) Wichita, Kansas

Wichita
OCT 20 1988
10-20-88
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-27-88

INV. NO. 22772

Signed *R. Phil Worley*
(TECHNICIAN)