

5 060132

10-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-21,266-00-00

NE NW SW, SEC. 9, T. 18 S, R. 10 W
2310 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Cody-Habiger Well # 4

Operator: John J. Darrah, Jr.

County Rice 106.28

Name & Address 412 E. Douglas, #1

Well Total Depth 3270' feet

Wichita, KS 67202

Conductor Pipe: Size 5-1/2" feet 3265/125 SX

Surface Casing: Size 8-5/8" feet 267

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Eng., Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: am Day: 7 Month: 10 Year: 19 88

Plugging proposal received from Joe Foelgner, Jr.

(company name) John J. Darrah, Jr. (phone)

were: Sand to 2950' and cap w/5 sx cement - pump 4 sx hulls, 25 sx gel, 1 sx hulls,
125 sx 60/40 poz 2% gel.

Plugging Proposal Received by Dist #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:12a Day: 7 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Sanded to 2950 and capped with 5 sx cement- pumped 4 sx
hulls, 25 sx gel, 1 sx hulls and 125 sx 60/40 pozmix 2% gel.

Perf: 3004-07'. PBD 3250'.

Max Pressure 750#. Shut in Pressure 500#.

Rec. 2224' of 5-1/2".

STATE CORPORATION COMMISSION

OCT 20 1988

10-20-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: HOWCO #763014

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

DATE 10-27-88

INV. NO. 22771

Signed R. Phil Worley
(TECHNICIAN)