

6-6 15-097-30122-0000

150

To: 1 051446  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 4/27/66  
C SW SW, SEC. 18, T 30 S, R 17 W/4E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5111  
Operator: Rockhold Engineering, Inc.  
Name & Address: P.O. Box 698  
Great Bend, KS 67530

660 feet from S section line  
4620 feet from E section line  
Lease Name Kane "C" Well # 1  
County Kiowa 166.17  
Well Total Depth 5113 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 533

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 6 Month: 6 Year: 1991

Plugging proposal received from Jim Rockhold  
(company name) Rockhold Engineering, Inc. (phone) 316-793-8471

were: 4 1/2" at 5110' w/150 sx cement, Perfs at 5065-67'  
1st plug sand back to 5000' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 p.m. Day: 6 Month: 6 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2766.85' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)  
JUN 10 1991 6-10-91  
CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 6-8-91  
INV. NO. 32255

Signed Richard W. Lacey (TECHNICIAN)