

1509520398000

RECEIVED
STATE CORPORATION COMMISSION

JUL 02 1976
7-2-76


CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Kingman County, Sec. 15 Twp. 28 Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Maurice L. Brown Company
Lease Name Clause #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 6/21/76 19____
Plugging completed 6/24/76 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3910 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	260	none
				5 1/2"	3908	3016'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3850' and set 5 sacks cement. Loaded casing with water, shot pipe at 3216', 3119', 3020', pulled 97 joints. Set rock bridge at 350' and ran 5 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 29th day of June 1976

My commission expires



Margaret Melcher
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED

JUN 09 1976

C. SUTTON II, Notary
Wichita, Kansas

Clouse #1
NE/4 Sec 15-28S-6W
Kingman County Kansas

Commenced: 4-2-75

Completed: 4-14-75

OPERATOR: MAURICE L. BROWN CO.

Depth		Formation	Remarks
From	to		
0	40	Red Rock	Ran 11 jts of used 8 5/8" csg set @ 260' Cemented w/ 225 sks posmix 3% CC PD @ 10:00 p.m. 4-2-75
40	261	Redbed-Shale	
261	700	Shale	
700	1090	Shale-Salt-Shells	
1090	1440	Lime-Shale	
1440	1600	Lime	Ran 126 jts of used 5 1/2" csg set @ 3908' Cemented w/ 150 sks 65/35 Posmix PD @ 1:07 p.m. 2-14-75
1600	1975	Lime-Shale	
1975	2580	Shale-Lime	
2580	2950	Lime-Shale	
2950	3090	Shale-Lime	
3090	3910	Lime	
	3910 TD		

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled NE/4 Sec 15-28S-6W Kingman County Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 22nd day of April, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I Have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC

My Commission Expires: November 29th, 1975.

