

15-155-03172-000


RECEIVED
10-26-37
OCT 26 1937
Strike out upper line when reporting plugging off formations.

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County. Sec. 25 Twp. 23 Rge. 4 (W)



Locate well correctly on above Section Plat

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE SE
Lease Owner. OLSON OIL COMPANY
Lease Name. J. Fast Well No. 5
Office Address. Box 408, Burrton, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole). OIL
Date, well completed. 4-9-37 193
Application for plugging filed. 9-4- 193 7
Application for plugging approved. 193
Plugging Commenced. 10-12-37 193
Plugging Completed. 10-16-37 193
Reason for abandonment of well or producing formation. Dry
If a producing well is abandoned, date of last production. 10-5-37 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Guy Wiershung
Producing formation. Chat Depth to top. 3275 Bottom. 3359 Total Depth of Well. 3359 Feet.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Chat	Oil & water	3355	3359	12 1/2"	261'	
				7"	3290'	3034' 5"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented hole back to 3200'. Filled hole with mud to 2800'. Wood Plug at 275'. Rock, mud and 15' of cement to 250'. Hole filled with mud to 22', dumped 10 sxs and cemented top of cellar.

PLUGGING
FILE # 25 23 40
BOOK 106 E-47

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Mr. S. A. Keefover,
Address Box 408, Burrton, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
S. A. Keefover (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Keefover

Box 408, Burrton, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23 day of October, 1937

My commission expires 4/20/38

G. F. Bryan Notary Public

15-155-03172-0000

OLSON OIL COMPANY
J. Fast # 5
NE NE SE, 25-23-4W
330' EL, 2970' NL.
RENO COUNTY, KANSAS

COMMENCED 3-10-37
COMPLETED 4-9-37
ELEVATION 1459'
Int. Prod. 35

0
147 Clay & sand
80 Shale
791 Shale & shs
932 Broken lime & shale
1114 Lime
1240 Lime, broken
1560 Shale
1646 Shale & shells
1847 Shale
72 Lime
1969 Shale & lime
2016 Lime, broken
76 Broken lime & shale
2158 Lime, broken
2202 Shale & lime
2465 Shale & shells
95 Sand
97 Shale
2555 Broken lime & shale
2637 Lime
44 Lime, sandy
2921 Lime
28 Lime, sandy
74 Lime
91 Lime & shale
3021 Shale
98 Shale & lime
3196 Shale
3276 Shale, var.
3385 Chat

CASING RECORD

12 $\frac{1}{2}$ " 40# 261' LW
7 " 24# 3290' LW

SAND RECORD

Top Chat 3275

Sho of Gas 3335-40

Show of oil & water 3355'

Water increased from 3360 to
3385'. 3 bailers water per Hr.

PLUGGING
FILE SE 25-23-4W
BOOK PAGE 106 LINE 47

Dumped 4 sxs cement
Total Depth - 3359'